

Date 12th Jun 2026

To
Mr. Vinay Yadav

Specifications for Construction Narayan Vihar, Jaipur

Area:

Total App Construction Area = 2050 Sqft

Height of Finished Ground Floor: 11'-0"

Height of Finished First Floor: 10'-10"

<u>CIVIL</u>	2250 Rs / Sft
Cement	Ambuja, Ultratech (Trade)
Rodi	Good quality Rodi.20 mm and 10 mm
Bajri	Banas Bajri
Steel	Rathi Saktiman, Jindal TMT
Masonry	Masonry in 1 st class of bricks in Kanota 9" masonry pilaster in 1: 5 and 4.5" masonry plaster in 1:5.
Pilaster	In 1:5 ratio of Cement: Sand of walls.
<u>FLOORING & STONE WORK</u>	
Inside Flooring	Floor Tiles Kajaria, Somani, Radon of max cost of 50 Rs/sft GST paid FOR on site

Staircase Granite	80 Rs/sft with GST & 110 Rs/sft for Kitchen
Toilets	Tiles upto 8'-0" ht Range 50 Rs/ Sqft. GST paid FOR (2'x4')
Driveway	Vitrified Tiles Range 40 Rs/ Sqft (EXTRA)
Outside Ramp	Cement Tiles 12 Rs/Sqft
Railing	Glass Railing on first floor for elevation Range 1100 Rs / rft at outside. Staircase railing round 4 pipe railing in 202 grade finish.
<u>ELECTRICAL</u>	
Wiring	Polycab , RR, Grade.
Switches	Basic Anchor peta, Legrand series or any std. make having 22Rs/switch cost.
MCB Box	MCB box of C&S make or equivalent with MCB.
Meter Panel	Not required
Electrical fixture	Exhaust fan of 1200 Rs for toilet & Kitchen.
AC piping	Papriwal copper pipe with Pvc Drainage pipe. Total Piping 150 rft Max.
<u>DOORS/WINDOWS</u>	
Doors	30 mm Wooden flush door 1 mm mica finish flush door 95/sft board and mica 1200 Rs/ sheet. With Mortice lock Range (1000)
Chaukhat	6"x2.5" stone chaukhat of Bijoliya
Windows	Domal 575 Rs/sft Including GST with Granite framing and edge polish.
Kitchen	Kitchen bottom furniture only with inotech drawer @ cost add 200000/- in above rate.
Wardrobe	Almirah in wooden shutter with mica finish (handle or lock included) without any type of drawer or locker Outer Mica Rs 1200/- sheet max. Partition in kota stone finish.
<u>PLUMBING</u>	
Plumbing	PVC & CPVC pipe of Supreme/ Astral make A- Class.
Sanitary Fittings - for toilets	Floor Mounted WC, Basin & Shower Mixer & all CP fittings of Parry ware/ Hind ware/ Cera, First and Second floor Range – 30000 Rs/ Toilet with geyser provision.
Sanitary Fittings - for Pantry	Kitchen with all fittings -8000 Rs/ kitchen including sink. Modular wooden work not included.
Overhead tank	1000 Liter tank for each floor with separate valve in Bathroom for each Toilet.
<u>POP/ PAINT</u>	
Internal POP	All Pop in plumb (fanti) line without cornice and Beading.

Internal Paint	Asian Premier plastic paint on ceilings and walls Asian enamel on grill and metal
----------------	---

External Paint	All external front paint in Asian ACE / texture paint and back area in Asian ACE paint or Perky Fine Roller finish
Birla White	Birla white would be done on all exterior area having plain paint
<u>MISCELLANEOUS</u>	
Water Proofing	In all toilets.
Safety Grill and Main Gate	Safety grill in 10 mm square bar and MS gate at roof terrace 350kg terrace floor SS/Ms Railing not include in 250 kg.
Solar Wiring & Meter	Solar Wiring provision with Meter provision in panel is to be given. It is of conduit for wiring only.
Water	Water charges in our scope.

Exclusions

Demolition Work extra
Roof Finish except cement / dhar Finish.
Rain Water Harvesting
Any type of false ceiling cost 220/- sft with paint and light included.
Water and electricity charges would be in client scope. If it is in Contractor's scope then add Rs 18/ Sqft for Electrical only. Meter Connection and Security deposit for connection is to be provided by the client.
False ceiling cost extra other than of toilets/ spaces to hide pipe.
Elevation cost extra, Any kind of stone & tiles/Aluminum / Metal work execution for elevation would be extra.
Any work outside Boundary wall will be extra other than Ramp
Any item which is no detailed would be charged @ 10% on Cost of material and labour.
CCTV, Water motor, Pressure Pump, Electrical panel excluded.
All cost mentioned is including GST.
Back side/ Double height Cut Out is not deductible.
No Side Passage work is included in this work other than repairing of damage.

NOTE:

1. Any difference in price beyond 5% is payable by party.
2. All Prices mentioned is GST paid.
3. No Wood Work of Kitchen.
4. If False Ceiling is to be done then Rs 220/ Sqft on Floor Area measurement would be extra including electrical wiring & Paint but without Light Fixtures.

PAYMENTS TERMS:-

1. 10% Advance
2. 10 % at 4' height.
3. 10 % Lintel level.
4. 10 % shuttering
5. 10 % Roof casting
6. 10 % Inner Pilaster
7. 10 % Outside Pilaster
8. 10 % On Flooring
9. 10 % At Paint in process
10. 5 % At Door & Window Completion
11. 5 % At completion of toilet / Kitchen / Electrical & Water supply work.